AN ISO 9001 & 14001 COMPANY

TENDER DOCUMENT

NIT No: PCO/BBSR/806/159

FOR

Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

VOLUME – III

Price Bid

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder/ Bidding Firm / Company :								
	PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else th			ected for this te	nder. Bidders are allowed to e	enter the Bidder Nam	e and Values only)	
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	7	13	14	15
1	Plastering Providing & finishing with 20 mm cement plaster of mix with 1.6 (1 cement: 6 coarse sand) Providing and Laving in noishion cement concrete or specimen grade excluding the cost of centering and shuttering. All work up to plurit level:	279.42	Sqm	INR		0.00	0.00	INR Zero Only
2	1.2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal sizederived from natural sources)	6452.63	cum	INR		0.00	0.00	INR Zero Only
3	WATER PROOFING WORK Waterproofing work on basement roof non tower area with landscaping above and green terrace for Command Control Centre Building as per detail scope of work & technical specification furnished below with SIKA/PIDILITE water proofing compound. Prior to take up the work agency have to submit method statement & TDS of all the material to be used for this work for taking up approval from appropriate authority. Work has to be completed in all respect along with supply all the all material, tooks, tackles, manpower, machineries & necessary civil works etc. and as per the direction of EIC. As per approved method statement agency has to prepare mock up sample to get approval from Client. **Basement roof non tower area with landscaping above and green terraces:* *Waterproofing membrane, geotextile and protection screed: * Providing and applying a Pully Bonded Liquid applied Hybrid Polyurea Polyurethane Waterproofing Membrane of total 1.50 mm thick system DFT having anti-root properties, to be applied in Min coats, over one coat of a solvent free two component poxy primer. No sand broadcast layer is permitted in the system. The system must be such that it is thixotropic, can be applied by airless spray, as well as the same product shall be tapplied on place and the properties of the system. The system must not be instant setting and shall have a min pot life of 15 mins to facilitate WHT measurement at every 10 to 15 Sqm during application to techet thickness and thereby not require destructive testing for thickness measurement. The Product shall be applied in accordance with the manufacturer's guidelines. Systems that contain Bitumen and/or those that are hot applied, or involve heating, shall not be permitted to be used. **How actor proofing membrane shall have following minimum properties: 1)Solid contents by volume: 100% 2)Prainal is extengible to the contain Bitumen and/or those that are hot applied, or involve heating, shall not be permitted to be used. **How actor proofing membrane and pr	1956.00	SQM	INR		0.00	0.00	INR Zero Only
4	Water Proofing on Sunken area for Command Control Centre Building as per detail scope of work & technical specification furnished below with SIKA/PIDILITE water proofing compound. Prior to take up the work agency have to submit method statement & TDS of all the material to be used for this work for taking up approval from appropriate authority. Work has to be completed in all respect along with supply all the all material, tooks, tackles, mapprover, machineries & necessary civil works etc. and as per the direction of EIC. As per approved method statement agency has to prepare mock up sample to get approval from Client. Sunken Area Water Proofing: Surface Preparations Surface to be free from frost, surface laitance and contamination free from loose aggregate or other sharp protrusions with fairly smooth finish for application of waterprocating prime the surface with water. Sore Packing Preparing the inside surface of core and PVC by roughening using suitable file to get better adhesion prior to packing works. Cleaning the surface by wire brushing followed water jot rough early to remove any laitance or loose flaky particles. Providing necessary formwork for packing the bore using suitable arrangement (depending upon site conditions). Applying a coat of styrene-butadine based polymer coating using any approved brand to enhance adhesion between the packing material and thotosay and the judge of over the pipe external side and packing the gap using non-shrink cement polymer based using Micro concrete up to the surface of the bore whilst the polymer is in tacky state. **Crowing: Coving at the junction of Isiah and vertical offsets with (M 12 mixed with approved bonding material at the dosage at the junction of Isiah and vertical offsets with (M 12 mixed with approved bonding material at the dosage at the junction of Isiah and vertical offsets with (M 12 mixed with approved bonding material at the dosage at the junction of Isiah and vertical offsets with (M 12 mixed with approved bonding material at the dosage at	862.00	SQM	inR		0.00	0.00	INR Zero Only
	Water Proofing treatment in underground water tank for Command Control Centre Building as per detail scope of work & technical specification furnished below with SIKA/PIDILITE water proofing compound. Prior to take up the work agency have to submit method statement & TDS of all the material to be used for this work for taking up approval from appropriate authority. Work has to be completed in all respect along with supply all the all material, tools, tackles, manpower, machineries. & necessary (vil) works etc. and as per the direction of EIC. As per approved method	1785.00	SQM	INR		0.00	0.00	INR Zero Only

Item Wise BoQ

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

ame of the	UBBSK/888101705 UT.29.UZ.2024										
ame of the idder/ Bidding irm / Company											
.1	PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY) (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)										
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT in Words			
1	2	4	5	12	7	13	14	15			
6	Providing and fixing 1st quality ceramic glazed wall tiles conforming tols: 15622 (thickness to be specified by the manufacturer), of approvedmake, in all colours, shades except burgundy, bottle green, black ofany size as approved by Engineer-in-Charge, in skirting risers of stepsand dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm,including pointing in white cement mixed with pigment of matching shadecomplete.	949.51		INR		0.00	0.00	INR Zero Only			
7	Polishing of Kota stone complete to provide smooth finish as per the direction of EIC complete.	512.50	SQM	INR		0.00	0.00	INR Zero Only			
8	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., completeSize of Tile 600x600 mm	1264.87	SQM	INR		0.00	0.00	INR Zero Only			
	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for littene platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement notar 1:4 (I center 1:4 coarse sand), lotins treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levelsGranite stone slab colour black, Cherry/Ruby red- Area of slab over 0.50 som	3951.21	SQM	INR		0.00	0.00	INR Zero Only			
	Providing & laying carpet flooring with approved sample materail and approved pattern. Rate inclusine Material sample approval & onward patter approval from client. Required levelling course to be laid for providing smooth finishine as ner the direction of ELC comolete.	1968.26	SQM	INR		0.00	0.00	INR Zero Only			
11	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per 15: 277 and consisting agle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37 mm, at 1200 mm centre to centre, one flange fixed to the engle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.L channel \$5x15x0.9 mm running at the spacing of 1200 mm centre to enter, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to enter, shall be fixed in a direction perpendicular to Linitermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.L wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of a wal screws of size 35 x 25 mm at 250 mm (c); including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter channel with the help of dry wall screws of size 25 x 25 mm at 253 mm c/c; including affinishing to a flush flinish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, spifils, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and disrouding the cost of making openings for light fittings, spifils, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and disrouding the cost of making openings for li	1023.17	SQM	INR		0.00	0.00	INR Zero Only			
12	Fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per 15: 277 and consisting or alge cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37 mm, at 1200 mm centre to centre, one flange fixed to the engle hangers of 25x10x0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.L channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.L intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.L wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws 9 e230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 5.5 x 55 mm at 25 x 55 mm at 25 mm 25 mm for, including and finishing to a flush finishing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 5.5 x 55 mm at 25 st 55 st 55 mm at 25 st 55 st 55 mm at 25 st 55	797.59	SQM	INR		0.00	0.00	INR Zero Only			
13	Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false celling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main Trunner suitably spaced at joints to get required length and of size 24x38 mm made for 03.3 mm thick (minimum) sheet, 200 mm long spaced between main True for some control of 3.3 mm (minimum) sheet, 200 mm long spaced between main True for minimum sheet to centre to centre to form a grid of 1200x600 mm and secondary cross Trol length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to from grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre, with 25mm long the perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of celling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to celling section and perimeter channel with the help of rawl plugs at 50 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound, jointing tapes, finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, gril		SQM	INR		0.00	0.00	INR Zero Only			

Sign and stamp of bidder 2 Sign and stamp of EPIL

Item Wise BoQ

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder/ Bidding Firm / Company								
	<u>PRICE SCHEDULE</u> (DOMESTIC TENDERS - RATES ARE TO GIVEN IN							
	(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the	e bidder is lial	ole to be rej	ected for this te	nder. Bidders are allowed to e		• •	
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	7	13	14	15
14	Providing and fixing GI Clip in Metal Ceiling System of 600x600 mm module which includes providing and fixing 'C' wall angle of size 20x30x20 mm made of 0.5 mm thick pre painted steel along the perimeter of the room with help of nylon sleeves and wooden screws at 300 mm center to centre, suspending the main C carrier of size 10x38x10 mm made of G.I steel 0.7 mm thick from the soffit with help of soffit cleat 37x27x25x1.6 mm, raw plugs of size 38x12 mm and C carrier suspension clip and main carrier bracket at 1000 mm c/c. Inverted triangle shaped Spring Tee having height of 24 mm and width of 34 mm made of GI steel 0.45 mm thick is then fixed to the main C carrier and in direction perpendicular to it at 60x16 mm centers with help of suspension brackets. Wherever the main C carrier and spring T have to join, C carrier and spring T connectors have to be used. All sections to be galvanized @ 120 gms/sqm (both side inclusive), fixing with clip in tiles into spring T with: GI Metal Ceiling Clip in plain Beveled edge global white color tiles of size 600x600 and 0.5 mm thick with 25 mm height, made of GI sheet having galvanizing of 100 gms/ sqm (both sides inclusive) and electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending.	1671 25	SQM	INR		0.00	0.00	INR Zero Only
15	CUBICAL PARTITION BOARD FOR TOILET RESCUEDATES, 2000 001 (HISN CDEE, 48239019) RESCO CUBICLE ZMS SS RESCHORD CORRECT SUBJECT STATES Size of Cubide: As per Drawing (W) X 1550mm (D) X 1933mm (H) Door Size: 1757mm (H) Divider Size: 1775mm (H) Divider Size: 1775mm (H) Overall Height Of Cubide: 1933mm (Including bottom Gap of 80mm) Accessories: Standard: Merino Make Aluminum, Stainless Steel - 304 Grade accessories) a) Aluminum 'To' Channel b) Aluminum 'F' Channel (Only Corner Unit) c) Aluminum Door Stopper Channel d) Aluminum To Po Stoper Channel d) Aluminum Top Rail e) SS Cast Hook 1) SS Privacy Thumb turn c/w Occupancy Indicator (g) SS Sprivacy Thumb turn c/w Occupancy I	32660.00		INR		0.00		INR Zero Only
	WPC JALI FIXING Fixing WPC jali at any height with necessary aluminium angle & square hollow section along with other fixing accessaries as per drawing including all tools/tackels complete.	1242.00	SQM	INR		0.00	0.00	INR Zero Only
17	Providing & Fixing WPC jali at any height with necessary aluminium angle & square hollow section along with other fixing accessaries as per drawing including all tools/tackels complete.	3082.00	SQM	INR		0.00	0.00	INR Zero Only
18	PAINTING WORK Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade: New work (two or more coats) over and including water thinnable priming coat with cement brimer cement brimer.	145.13	SQM	INR		0.00	0.00	INR Zero Only
19	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	110.58	SQM	INR		0.00	0.00	INR Zero Only
20	Finishing walls with Acrylic Smooth exterior paint of required shade New work (Two or more coat applied @ 1.67 ltr/10 sqmover and including priming coat of exterior primer applied@ 2.20 kg/10 sqm)	148.97	SQM	INR		0.00	0.00	INR Zero Only
21	White washing with lime to give an even shade : New work (three or more coats)	28.97	SQM	INR		0.00	0.00	INR Zero Only
22	STRUCTURAL GLAZING WORK Trameless Glass Door with 12mm thick toughened clear glass shutters, anchor fastener, BR soft nose seal, modular design, including internal cover etc. and as per technical specification comolete as per the instruction of BIC.	8100.00		INR		0.00		INR Zero Only
23	Provoding & fixing Aluminium Louvers at External face. The scope include preperation & submission of fabrication drawing to Client for taking approval prior to start execution.	6200.00	SQM	INR		0.00	0.00	INR Zero Only

Sign and stamp of bidder 3 Sign and stamp of EPIL

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder/ Bidding								
Firm / Company :								
	PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN							
	(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else th	e bidder is lial	ole to be rej	cted for this ter	nder. Bidders are allowed to e	enter the Bidder Nam	e and Values only)	
SI. No.					BASIC RATE (including	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
	Item Description	Quantity	Units	Quoted Currency in	Transportation Insurance, F.O.R.) In Figures To be	in Rs. P	in Rs. P	
	Society.	Quantity	oo	INR / Other Currency	entered by the Bidder in Rs. P			
1	2	4	5	12	7	13	14	15
24	Providing and Itsing factory made single extruded WPL (Wood Polymer Composite) solid door/window/clerestory windows &desertory other Prames/Lowkhat comprising of virgin PVLpolymer of K value S8-60 (Suspension Grade), calciumcarbonate and natural fibers (wood powder/rice busk/wheathusk) and not additives (maximum toxicity index of 126r 100 gms). Bidbrietade with miter joints after applying PVCsolvent cement and screwed with full body threaded starbeaded SS screws having minimum frame density of 750 kg/cum, screw withdrawal strength of 2200 N (Face) & 1100 N (Edge), minimum compressive strength of 58 N/mm2, modulus of elasticity 900 N/mm2 and resistance to spread of flame ofClass A category with property of being termite/borer proof, water/ministure proof and fire retardant and fixed in positionwith MS hold fast/jugy/SS dash fasteners of required dia andlength complete as per direction of Engineer1-n-Charge Note: For WPC Solid door/window frames, minus Smm tolerance in dimensions i.e depth and width of profile shall be acceptable. Variation in profile dimensions on plus side shall be acceptable but no extra payment on this account shall be made. Frame size 65 x 125 mm	1114.02	metre	INR		0.00	0.00	INR Zero Only
25	Providing and fixing factory made single extruded WPC (Wood Polymer Composite) solid plain flush door shutter of required size comprising of virgin polymer of K value 58-60 (Suspension Grade), calcium carbonate and natural fibers (wood powder/ rice husk/wheat husk) and non toxic additives (maximum toxicity index of 12 for 100 gms) having minimum density of 650 kg/cum and screw withdrawal strength of 1800 N (Face) & 900 N (Edge), minimum compressive strength 50 N/mm2, modulus of elasticity 850 N/mm2 and resistance to spread of flame of Class A category with property of being termite/bore proof, water/moisture proof and fire reardant and fixing with stainless steel butt thinges of required size with necessary full body threaded star headed counter sunk SS screws, all as per direction of Engineer-In- Charge. (Note: stainless steel butt hinges and necessary SS screws shall be paid separately) - 30 mm thick	3530.36	sqm	INR		0.00	0.00	INR Zero Only
26	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part 1) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 30 mm thick including ISI marked Stainless Stee but thingeswith necessary screws sqm	2516.52	sqm	INR		0.00	0.00	INR Zero Only
27	Providing & fixing Aluminium louvers (300X300) at toilet door including all tools tackels etc.	1500.00	EACH	INR		0.00	0.00	INR Zero Only
	Providing and fixing stainless steel (Grade 304) railing made of Hollowtubes, channels, plates etc., including welding, grinding, buffing, polishingand making curvature (wherever required) and fitting the same withnecessary stainless steel auts and bolts complete, [/c fixing the railingwith necessary accessories & stainless steel dash fasteners, stainlesssteel bolts etc., of required size, on the top of the floor or the side obvists lab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel membershall be considered.)		KG	INR		0.00	0.00	INR Zero Only
29	Cleaning of under ground sump, Over Head R.C.C. Tank (independent staging) including disposal of slit and rubbish, all as per direction of Engineer-in-Charge. The cleaning shall consist following operation. (I) Tank shall be emptied of water by pumping & bottom shall be cleaned of slit and other deposits.C66-: (ii) Entire surface area of the sump shall then scrubbed thoroughly with wire brush etc. and pressure washed with water. iii) Chlorination of R.C. Internal surface by liquid chlorine. iv) The treated surface shall be dried using air jetting and all loose particles shall be removal from the surface. Finally the surface shall be treated with ultraviolet radiation etcas per direction of Engineer-in-Charge. sqm 71.30	63.66	sqm	INR		0.00	0.00	INR Zero Only
30	Removal of scaffolding upto [G+5] level of the building & stacking of scaffolding materall at site within a initial lead of 100mtr including all manpower, tools & tackles as required maining proper safety arrangement & as per the instruction of Engineer-In-Charge [The elevational area of the scaffolding shall be measuredfor payment purpose]	101.78	SQM	INR		0.00	0.00	INR Zero Only
	Dismantling concrete /morter rubbis by breaker or manually and Cleaning debris, rubbish & dispose the material as per the instruction of Engineer-In-Charge including all manpower, tools & tackles etc. complete.	40.00	sqm	INR		0.00	0.00	INR Zero Only
32	B) Sanitary & Plumbing work Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, I/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc. 20 mm nominal dia Pipes	283.90	MTR	INR		0.00	0.00	INR Zero Only
	25 mm nominal dia Pipes	339.83		INR		0.00		INR Zero Only
	32 mm nominal dia Pipes 40 mm nominal dia Pipes	438.98 594.92		INR INR		0.00		INR Zero Only INR Zero Only
36	50 mm nominal dia Pipes	4751.00	MTR	INR		0.00	0.00	INR Zero Only
	65 mm nominal dia Pipes	8080.00		INR		0.00		INR Zero Only
38	80 mm nominal dia Pipes Providing and fixing of following dia UPVC pipes including with all fittings like bend. Tee, elbow, offsets etc. and the same fixed on wall or floor with holder bat clamps screw in all floors as per specification &	1055.08 4006.78	MTR	INR		0.00	0.00	INR Zero Only
39	revoking and using or nonwing all over C pipes including which an integrate Delta, rec, rouw, prises exc. and the same need on want of noor with noder out damps seew in an incors as per specification at direction of Engineer-in-charge. 110 mm	1000.70	MTR	INR		0.00		INR Zero Only
40	Supply & fixing Wash Basin (480X480X200mm) model No. Flair C0464 along with all necessary fixing arrangement, labour, tools & tackels etc. complete	2322.63	EACH	INR		0.00		INR Zero Only
41	Supply & fixing wall hung Wash Basin (580X480X400) for Handicapped Toilet Hindware make model No. KYLIS 91053 along with all necessary fixing arrangement, labour, tools & tackels etc. complete	18407.59	EACH	INR		0.00		INR Zero Only
42	Supply & fixing Basin Mixer Jaquar make model No. FLR-15001BPM along with all necessary fixing arrangement, labour, tools & tackels etc. complete	4333.94	EACH EACH	INR INR		0.00	0.00	INR Zero Only INR Zero Only
	Supply & fixing Sink cock with Mixer Jaquar make & model No. FLR-5309N along with all necessary fixing arrangement, labour, tools & tackels etc. complete Supply & fixing Waste coupling 100 mm size ALD-705 for basin along with all necessary fixing arrangement, labour, tools & tackels etc. complete	41009.32 512.63		INR		0.00		INR Zero Only INR Zero Only
	Supply & Riving Bottle Tray Javar make & model no. ALLD-760 L 250x190 mm along with all necessary fixing arrangement, valour, toous & cackets ext. Complete Supply & Riving Bottle Tray Javar make & model no. ALLD-760 L 250x190 mm along with all necessary fixing arrangement, labour, tools & tackets etc. complete	1724.26		INR		0.00	0.00	INR Zero Only
	Supply & fixing waste pipe for basin along with all necessary fixing arrangement, labour, tools & tackels etc. complete	55.93		INR		0.00	0.00	INR Zero Only

Item Wise BoQ

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder/ Bidding Firm / Company PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY) (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

SI.								
No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	7	13	14	15
47	Supply & fixing EWC Commode (520X370X360) Hindware make model no. Elegance Neo 20109 along with all necessary fixing arrangement, labour, tools & tackels etc. complete	8263.99		INR		0.00		INR Zero Only
	Supply & fixing Flush Valve dual flow 32mm size (concealed body) shut off provision & rectangular dual flush plate ABS chrome plated (3.00 /6.00 LTS per flush) model no. FLV1085DFP along with all	3774.72	DAGW					
48	necessary fixing arrangement, labour, tools & tackels etc. complete		EACH	INR		0.00	0.00	INR Zero Only
49	Supply & fixing Hindware make Urinal Commode (300X330X450) model No.Corto 60023 (Top inlet) along with all necessary fixing arrangement, labour, tools & tackels etc. complete	3383.27		INR		0.00		INR Zero Only
50	Supply & fixing Toilet paper Holder model no. ACN-1153S & ALD-805B long braided hose 450mm along with all necessary fixing arrangement, labour, tools & tackels etc. complete	1467.95		INR		0.00		INR Zero Only
51	Supply & fixing Geyser Elena Vertical (25 ltr) Jaquar make along with all necessary fixing arrangement, labour, tools & tackels etc. complete	12725.31		INR		0.00		INR Zero Only
52	Supply & fixing Soap Dispencers jaquar make & model no. ACN-1137N along with all necessary fixing arrangement, labour, tools & tackels etc. complete	1374.75		INR		0.00		INR Zero Only
53	Supply & fixing Towel Rings jaquar make & model no. ACN-1121N along with all necessary fixing arrangement, labour, tools & tackels etc. complete	1211.65		INR		0.00		INR Zero Only
54	Supply & fixing PVC Connection Pipe 24" along with all necessary fixing arrangement, labour, tools & tackels etc. complete	109.98	EACH	INR		0.00	0.00	INR Zero Only
55	Supply & fixing Angle Valve model no. ARI-39053 jaquar make for wash basin, Kitchen sink & Gyser along with all necessary fixing arrangement, labour, tools & tackels etc. complete	1071.83	EACH	INR		0.00	0.00	INR Zero Only
56		73,33	EACH	INR		0.00		INR Zero Only INR Zero Only
55	Supply & fixing Floor Trap cromium plated 5" dia along with all necessary fixing arrangement, labour, tools & tackels etc. complete Supply & fixing Two way 8ib cock jaquar make model no. ARI-39041 along with all necessary fixing arrangement, labour, tools & tackels etc. complete	73.33 1817.46		INR		0.00		INR Zero Only
58	Supply & rixing Health Faucet model no. ALD 579 of Jaquar make for EWC along with all necessary fixing arrangement, labour, tools & tackets etc. Complete Supply & Rixing Health Faucet model no. ALD 579 of Jaquar make for EWC along with all necessary fixing arrangement, labour, tools & tackets etc. Complete	1607.76	EACH	INR		0.00		INR Zero Only
59	Supply & Rixing Health Faucet mouer no. ALD 979 or Jaquar interest not supply with all necessary fixing an armeters any none of active section of the supply of Rixing Urinal Push Cock model no. PRS-077 along with all necessary fixing arrangement, labour, tools & tackels etc. complete Supply & Rixing Urinal Push Cock model no. PRS-077 along with all necessary fixing arrangement, labour, tools & tackels etc. complete	2376.67		INR		0.00		INR Zero Only
	Supply & fixing Shower OHS -1603 150mm dia & shower arm model No. SHA-4791450 20mm/M350mm long round shape with 90 degree bend for wall mounted shower with flange along with all necessary	4636.86				0.00	0.00	THE LOS ONLY
60	Spire arrangement, labour, tools & tackels etc. complete	1030.00	EACH	INR		0.00	0.00	INR Zero Only
61	Supply & fixing Stainless Steel Kitchen sink model No. CAN-1153S (24X18") along with all necessary fixing arrangement, labour, tools & tackels etc. complete	2609.69	EACH	INR		0.00		INR Zero Only
62	Supply & fixing Sink Coupling along with all necessary fixing arrangement, labour, tools & tackels etc. complete	502.52	EACH	INR		0.00		INR Zero Only
63	Supply & fixing Drain pipe along with all necessary fixing arrangement, labour, tools & tackels etc. complete	55.93		INR		0.00	0.00	INR Zero Only
64	Supply & fixing Sink Mixer Jaquar make model no. FLR5309N with Regular Swinging Spout (Wall Mounted Model) With Connecting Legs & Wall Flanges along with all necessary fixing arrangement, labour, tools	4333.94		INR				•
64	& tackels etc. complete		EACH	INK		0.00	0.00	INR Zero Only
65	Supply & fixing sink cock Sink Cock with Regular Swinging Spout (Wall Mounted Model) With Wall Flange jaquar make model no. FLR-5347N along with all necessary fixing arrangement, labour, tools & tackels	2050.48	EACH	INR				
00	etc. complete		EACH	INK		0.00	0.00	INR Zero Only
66	Supply & fixing Wall mixture with telephone shower arrangement, connecting legs & wall flange but without crutch & telephone shower Jaquar make & model No. FLR 5217N along with all necessary fixing	5685.38	EACH	INR				
	arrangement, labour, tools & tackels etc. complete					0.00		INR Zero Only
67	Supply & fixing Hand Drier ASKON make & model No. AS-25-IR(W) size 290mmX220mmX145mm along with all necessary fixing arrangement, labour, tools & tackels etc. complete	19796.31	EACH	INR		0.00	0.00	INR Zero Only
68	Providing and laying Urinal Partition (400 mm x 1,200 mm) of machine cut and both side machine pre-polished Granite Stone slab, Type: W14, 19 mm thick of size as per drawings set on backing coat of	4179.00	EACH	INR				ND7 01
	cement mortar 1:3 not exceeding 19 mm thick, including pointing with matching cement paste with pigmented additives to match the shade of the slab CJ ELECTRICAL WORKS					0.00	0.00	INR Zero Only
69	Wiring Supply and drawing following of FRLS PVC insulated copper conductor, single core cable in existing surface/recessed steel/PVC conduit including identifying existing conduits, minor repairing etc as required as per approved drawing to complete the job as directed by engineer-in-charge. 2 X 1 5 sq. mm + 1 X 1 5 sq. mm earth wire	1200.00	Mtr	INR		0.00	0.00	INR Zero Only
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	850.00		INR		0.00		INR Zero Only
71	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	520.00	Mtr	INR		0.00	0.00	INR Zero Only
71 72	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm	520.00 220.00	Mtr Mtr	INR INR		0.00	0.00 0.00	INR Zero Only INR Zero Only
71 72 73	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 6 sq. mm	520.00 220.00 220.00	Mtr Mtr Mtr	INR INR INR		0.00 0.00 0.00	0.00 0.00 0.00	INR Zero Only INR Zero Only INR Zero Only
71 72 73	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 6 sq. mm 4 X 10 sq. mm	520.00 220.00	Mtr Mtr Mtr	INR INR		0.00	0.00 0.00 0.00	INR Zero Only INR Zero Only
71 72 73	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 6 sq. mm 4 X 10 sq. mm 4 X 10 sq. mm 5 X 10 sq. mm 6 X 10 sq. mm 6 X 10 sq. mm 7 Supplying and fixing of following sizes of Heavy class PVC FRLS conduit along with accessories in surface/recess including cutting the wall and making good the samein case of recessed conduit as required. Make-AKG/Percision 20 mm	520.00 220.00 220.00 150.00 300.00	Mtr Mtr Mtr Mtr Mtr	INR INR INR INR INR		0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	INR Zero Only INR Zero Only INR Zero Only INR Zero Only
76	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 6 sq. mm 4 X 16 sq. mm 4 X 10 sq. mm 5 x 10 sq. mm 6 x 10 sq. mm 6 x 10 sq. mm 7 x 10 sq. mm 8 x 10 sq. mm 8 x 10 sq. mm 9 x 10 sq. mm 1 x 10 sq. mm 2 x 10 sq. mm 3 x 10 sq. mm 1 x 10 sq. mm 2 x 10 sq. mm 3 x 10 sq. mm 3 x 10 sq. mm 4 x 10 sq. mm 4 x 10 sq. mm 8 x 10	520.00 220.00 220.00 150.00 300.00	Mtr Mtr Mtr Mtr Mtr	INR INR INR INR INR INR		0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	INR Zero Only
71 72 73 74 75	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 6 sq. mm 4 X 10 sq. mm 5 X 10 sq. mm 6 X 10 sq. mm 6 X 10 sq. mm 6 X 10 sq. mm 7 Supplying and fixing of following sizes of Heavy class PVC FRLS conduit along with accessories in surface/recess including cutting the wall and making good the samein case of recessed conduit as required. Make-AKG/Percision 7 0 mm 7 25 mm 7 32 mm	520.00 220.00 220.00 150.00 300.00	Mtr Mtr Mtr Mtr Mtr	INR INR INR INR INR		0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00	INR Zero Only INR Zero Only INR Zero Only INR Zero Only
71 72 73 74 75	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 5 sq. mm 4 X 10 sq. mm 5 X 10 sq. mm 6 X 10 sq. mm 6 X 10 sq. mm 7 X 10 sq. mm 7 X 10 sq. mm 8 X 10 sq. mm 9 X 10 sq. mm 1 X 10	520.00 220.00 220.00 150.00 300.00	Mtr Mtr Mtr Mtr Mtr Mtr Mtr Mtr Mtr	INR INR INR INR INR INR		0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00	INR Zero Only
71 72 73 74 75 76 77	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 4 sq. mm 4 X 5 sq. mm 4 X 5 sq. mm 4 X 5 sq. mm 6 X 5 sq. mm 6 X 5 sq. mm 8 Supplying and fixing of following sizes of Heavy class PVC FRLS conduit along with accessories in surface/recess including cutting the wall and making good the samein case of recessed conduit as required. Make-AKG/Percision 20 mm 32 mm 32 mm 32 mm	520.00 220.00 220.00 150.00 300.00 450.00	Mtr	INR INR INR INR INR INR INR		0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00	INR Zero Only
71 72 73 74 75 76 77 78	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 4 sq. mm 4 X 5 sq. mm 4 X 5 sq. mm 5 X 5 sq. mm 5 X 10 sq. mm 6 X 10 sq. mm 7 X 10 sq. mm 7 X 10 sq. mm 8 X 10 sq. mm 10 mm	520.00 220.00 220.00 150.00 300.00 450.00 150.00	Mtr	INR INR INR INR INR INR INR INR		0.00 0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00	INR Zero Only
71 72 73 74 75 76 77 78	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 0 sq. mm 4 X 10 sq. mm 5 X 10 sq. mm 6 X 10 sq. mm 6 X 10 sq. mm 7 X 10 sq. mm 7 X 10 sq. mm 8 X 10 sq. mm 9 X 10 sq. mm 1 X 10	520.00 220.00 220.00 150.00 300.00 450.00 500.00	Mtr	INR		0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	0.00 0.00 0.00 0.00 0.00 0.00 0.00	INR Zero Only
71 72 73 74 75 76 77 78	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 4 sq. mm 4 X 5 sq. mm 4 X 5 sq. mm 4 X 5 sq. mm 4 X 6 sq. mm 5 xypplying and fixing of following sizes of Heavy class PVC FRLS conduit along with accessories in surface/recess including cutting the wall and making good the samein case of recessed conduit as required. Make-AKG/Percision 20 mm 32 mm 5 xypplying and fixing of following sizes of medium class Steel conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. Make-AKG 20 mm 25 mm 25 mm 26 xypplying and fixing of following sizes of medium class Steel conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed conduit as required. Make-AKG 20 ypply and fixing 3 pin, 5A ceiling rose on the junction box including connetions ets. As required.	520.00 220.00 220.00 150.00 300.00 450.00 150.00 500.00	Mtr	INR		0.00 0.00 0.00 0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	INR Zero Only
71 72 73 74 75 76 77 78 79 80 81	2 X 4 sq. mm + 1 X 4 sq. mm earth wire 4 X 4 sq. mm 4 X 10 sq. mm 5 X 10 sq. mm 6 X 10 sq. mm 7 X 10 sq. mm 7 X 10 sq. mm 8 X 10 sq. mm 9 X 10 sq. mm 9 X 10 sq. mm 1 X 10 sq. mm 2 sq. mm 2 sq. mm 2 sq. mm 2 sq. mm 3 sq. mm 3 sq. mm 3 sq. mm 3 sq. mm 4 x 10 sq. mm 5 sq. mm 6 x 10 sq	520.00 220.00 220.00 150.00 300.00 450.00 150.00 500.00 380.00 180.00	Mtr	INR		0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	0.00 0.00 0.00 0.00 0.00 0.00 0.00 0.0	INR Zero Only

Sign and stamp of bidder 5 Sign and stamp of EPIL

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder Bidding Firm / Company : | PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY) (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

	(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else th	e bidder is ilabi	e to be rej	ected for this ter	nder. Bidders are allowed to e	enter the bidder Nam	e and values only)	
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	7	13	14	15
	4 Module (100mmX75mm)	20.00	Nos	INR		0.00		INR Zero Only
	6 Module (100mmX75mm)	20.00	Nos	INR		0.00		INR Zero Only
	8 Module (100mmXT5mm) Supplying and fixing following modular switch/socket on the existing modular plate & switch box including identifying existing wires, providing of pvc tube ferrule as per circuit, connections but excluding modular plate etc. as required.Make-Legrand-Lyncus 50 A switch	18.00 948.00	Nos	INR		0.00		INR Zero Only
89	15/16 A switch	250.00	Nos	INR		0.00		INR Zero Only
	3 pin 5/6 A socket outlet	464.00	Nos	INR		0.00		INR Zero Only
91	6 pin 15/16 A socket outlet	250.00	Nos	INR		0.00	0.00	INR Zero Only
92	Supply and fixing following Modular base & cover plate on existing modular metal box etc. as required. 1 or 2 Module	280.00	Nos	INR		0.00		INR Zero Only
	3 Module	382.00	Nos	INR		0.00		INR Zero Only
94	4 Module 6 Module	35.00 180.00	Nos Nos	INR INR		0.00		INR Zero Only INR Zero Only
	5 MOGUIE R Module	28.00	Nos	INR		0.00		INR Zero Only
97	TW antenna socket outlet	5.00	Nos	INR		0.00		INR Zero Only
	Modular blanking plate	22.00	Nos	INR		0.00		INR Zero Only
	DB, MCBS, RCCBs Etc. Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board(Double door), 415 volts, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator) Make-L&T 4 way (4 + 12), Double door (VTPN)	4.00	Nos	INR		0.00		INR Zero Only
100	8 way (4 + 24), Double door (VTPN)	4.00	Nos	INR		0.00	0.00	INR Zero Only
101	Supplying and fixing SA to 32A rating, 240/415 volts, 10 kA, "C" curve,miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with identifying existing wires, wire dressing, providing pvr tube ferrule as per circuit, fugs, connections, testing and commissioning etc. as required. as directed by engineer-in-charge.Make-L&T 6 A to 32 A ratings. SP MCB-C" curve, 10 KA breaking capacity	742.00	Nos	INR		0.00	0.00	INR Zero Only
	6 A to 32 A ratings , TPN MCB, "C" curve, 10 KA breaking capacity	98.00	Nos	INR		0.00		INR Zero Only
	40/63 A ratings , TPN MCB,"C" curve, 10 KA breaking capacity	17.00	Nos	INR		0.00		INR Zero Only
104	100 A ratings , TPN MCB,"C" curve, 16 KA breaking capacity	2.00	Nos	INR		0.00		INR Zero Only
	25 A rating, 2 pole RCCB, 30mA/100mA as per requirment.	4.00	Nos	INR		0.00		INR Zero Only
	40 A rating, 2 pole RCCB, 30mA/100mA as per requirment.	38.00	Nos	INR		0.00		INR Zero Only
107	83 A rating, 2 pole RCCB, 30 mA 100 A rating, 2 pole RCCB, 30 mA	15.00 4.00	Nos Nos	INR INR		0.00		INR Zero Only INR Zero Only
	Too Ar laung, 2 pion RCCB, 30 mA	25.00	Nos	INR		0.00		INR Zero Only
	Exply and fixing 20A, 240V, SPN industrial type socket outlet, with 2 pole and earth mental enclosed plug top alongwith 20 A "C" curve, SP, MCB in sheet steel encloser, on surface or recess, with chained							· · · · · · · · · · · · · · · · · · ·
110	metal cover for the socket outlet and complete with connection, testing & commissioning etc as required.	3.00	Nos	INR		0.00	0.00	INR Zero Only
111	supply and fixing 304, 415V, TPN industrial type socket outlet, with 4 pole and earth mental enclosed plug top alongwith 30 A "C" curve, TPMCB in sheet steel encloser, on surface or recess, with chained metal cover for the socket outlet and complete with connection, testing & commissioning etc as required.	8.00	Nos	INR		0.00	0.00	INR Zero Only
112	CABLE TRAY CABLING AND END TERMINATION etc. Supplying and installing following size of perforated Hot Dipped Galvanised from cable tray with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with G.1 suspenders MS Angel including G.1 bolts & nuts, etc as required.as directed by engineer-in-charge.	120.00	Mtr	INR		0.00	0.00	INR Zero Only
113	150 mm width X 50 mm delpth X 1.6 mm thickness	80.00	Mtr	INR		0.00	0.00	INR Zero Only
114	300 mm width X 60 mm depth X 1.6 mm thickness	60.00	Mtr	INR		0.00	0.00	INR Zero Only
115	Supply, loading, transportation unloading at site, storages at site, shifting from storage place to site of following sizes of XLPE insulated PVC sheathed, outersheath FRLS, Aluminium conductor flat strip armoured power cable of 1.1 KV grade conforming to IS amended upto date and as per specifications.	200.00	Mtr	INR		0.00	0.00	INR Zero Only
116	4C x 10 Samm.	350.00	Mtr	INR		0.00	0.00	INR Zero Only
	3.5 C x 25 Sqmm.	85.00	Mtr	INR		0.00		INR Zero Only
	3.5C x 35 Sqmm.	65.00	Mtr	INR		0.00		INR Zero Only
	3.5C x 50 Sqmm.	80.00	Mtr	INR		0.00		INR Zero Only
120	3.5C x 240 Sqmm.	50.00	Mtr	INR		0.00	0.00	INR Zero Only
121	Laying and fixing of one number PVC insulated and PVC sheathed / XLPE power cable of 1.1 KV grade of following size on cable tray as required. Upto 35 sq.mm	400.00	Mtr	INR		0.00		INR Zero Only
122	Above 35 sq.mm and upto 95 sq. mm	401.00	Mtr	INR		0.00		INR Zero Only
	Above 185 sq.mm and upto 400 sq. mm	600.00	Mtr	INR		0.00	0.00	INR Zero Only
123	Supplying, laying and making end termination of one number PVC insulated armoured and PVC sheathed Cu conductor power cable of 1.1 KV grade of following size cables as required to complete the job.[MAKE-Polycab]	100.00	Mtr	INR		0.00	0.00	INR Zero Only

Sign and stamp of EPIL

Item Wise BoQ

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder/ Bidding Firm / Company PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY)

	(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else th	io biddor io nab	ie to be rej	ected for this ter	ider. Bidders are allowed to e			
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	7	13	14	15
126	2 core 2.5 sqmm copper armoured cable	80.00	Mtr	INR		0.00	0.00	INR Zero Only
127	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed/XLPE aluminium cable of 1.1 KV grade as required.mentioned size cable.	15.00	Nos	INR		0.00	0.00	INR Zero Only
400	4C x 10 Samm.	15.00	N	INR		0.00	0.00	INR Zero Only
128 129	46 x 16 Sqmm. 3.56 x 25 Sqmm.	20.00	Nos Nos	INR		0.00		INR Zero Only
130	5.50 x 22 Sqmm. 3.50 x 35 Sqmm.	24.00	Nos	INR		0.00		INR Zero Only
131	5.50 x 50 sqinii. 3.50 x 50 samm.	10.00	Nos	INR		0.00		INR Zero Only
		46.00		INR		0.00		
132	3.50 x 240 Sqmm. EARTHING INSTALLATION	40.00	Nos	INK		0.00	0.00	INR Zero Only
133	Supplying and laying of G.l/copper Earth strip on surface or in recess for connections etc. as required. 25 mm X 6 mm G.l. strip	80.00	Mtr	INR		0.00	0.00	INR Zero Only
134	40 mm X 6 mm G.I. strip	40.00	Mtr	INR		0.00	0.00	INR Zero Only
135	50 mm X 6 mm G.I. strip	100.00	Mtr	INR		0.00		INR Zero Only
136	26 mm X 6 mm G.I. copper	130.00	Mtr	INR		0.00		INR Zero Only
137	Providing and fixing 6 SWG dia G.I wire on surface or in recess for loop earthing as required.	30.00	Mtr	INR		0.00	0.00	INR Zero Only
138	Providing and fixing 16 SQMM Copper Wire on surface or in recess for earthing as required.	70.00	Mtr	INR		0.00	0.00	INR Zero Only
139	Installation, Testing & Commissioning of 50mm dia GI Pipe earthing including excavation, charcoal, salt, pit chamber with cover etc as required.	6.00	Nos	INR		0.00		INR Zero Only
140	LIGHT FITTING FIXTURES Supplying, Installation, Testing & Commissioning of following type light fixtures. Make-Wipro LI22-511-XXX-65-AL2	148.00	Nos	INR		0.00	0.00	INR Zero Only
	[40WLED BATTEN] LIDG-111-XXX-57-XX							
141	LOUG-11-XAX-9-XAX (9W RECESSED LED DOWNLIGHT)	35.00	Nos	INR		0.00	0.00	INR Zero Only
142	CRC010R038HP57DAG2 [GWO DAID IMMABLE RECESSED 22 LED PANEL]	2.00	Nos	INR		0.00	0.00	INR Zero Only
143	LD06-171-XXX-2765	12.00	Nos	INR		0.00	0.00	INR Zero Only
	LISW TUNABLE DIMMABLE RECESSED LED DOWNLIGHT)							
144	LD06-171-XXX-575MG1	1.00	Nos.	INR		0.00		INR Zero Only
145	[106:171.XXX:57-XX] [CRC0108038H97G2 [mmaculate+ :	4.00	Nos.	INR		0.00		INR Zero Only
146	CRUCIONISONPS/1/2 immacusite*: Recess Mounted 2ft x 2ft tED jumniare with Diffuser	2.00	Nos.	INR		0.00		INR Zero Only
147	LL20-221-XXX-65NE3 TrimLED Neo - 4FT LED Batten	5.00	Nos.	INR		0.00		INR Zero Only
148	LM34-251-XXX-57RMCG1	10.00	Nos.	INR		0.00		INR Zero Only
149	GLPSDA - Smart Daylight PIR occupancy detector, with DALI output	5.00	Nos.	INR		0.00		INR Zero Only
150	Cove Light Driver LG40-050	1.00	Nos	INR		0.00		INR Zero Only
151	Cove Light-LS06-010-120-30-50 + L640-050	5.00	Nos	INR		0.00		INR Zero Only
152	9W Bulk Head Light-LW07-141-XXX-57-G1	34.00	Nos	INR		0.00		INR Zero Only
153	PIR Occupancy sensor-GLPS01R010A	25.00	Nos	INR		0.00		INR Zero Only
154	Exit Lights-Make-Prolite	40.00	Nos	INR		0.00		INR Zero Only
155	Installation, Testing & Commissioning of Decorative type light fixtures in Surface/False ceiling as per approved drawing/ as directed by engineer-in-charge including connectors etc as required.	913.00	Nos	INR		0.00	0.00	INR Zero Only
156	DG Set Balance works SITC of Indoor type DG Metering Panel with 2mm thick sheer powder coated for 625 KVA DG Set 3phase, 4wire Static LT CT Energy meter-03nos, 1000/ SA Class 1.0-03 nos, STL Testing Charges-CT's & Meter MS base frame, Test Reports et as required for installation etc. to complete the work in all respect.	2.00	Nos	INR		0.00	0.00	INR Zero Only
157	TSCI insulation and claudding for exhaust ducting inside genset room area and outside using 50 mm thick rockool of density 120 Kg/ M3 & 24 SWG Aluminium Sheet for both the Gas Generator sets 250 mm (NB) dia Exhaust Pipe	8.00	Rm	INR		0.00	0.00	INR Zero Only
158	400 mm (NB) dia Exhaust Pipe	10.00	Rm	INR		0.00		INR Zero Only
159	SITC of all accessories such as flanges, stainless steel flexible bellows etc. and fixing/ supporting arrangement etc. as required to complete the work.	1.00	Ls	INR		0.00	0.00	INR Zero Only
160	Supply, Laying and end termination of one number PVC insulated and PVC sheathed FRLS / XLPE copper control cable of 1.1 KV grade of following size in the existing cable tray/DWC pipe as required. 22 x 2.5 Sqmm	150.00	Mtr	INR		0.00	0.00	INR Zero Only
161	4C x 2.5 Sgmm	150.00	Mtr	INR		0.00	0.00	INR Zero Only
162	6C x 2.5 Sqmm (Shielded Cable)	120.00	Mtr	INR		0.00		INR Zero Only
163	24C x 2.5 Sqmm (Shielded Cable)	120.00	Mtr	INR		0.00		INR Zero Only
164	Lightning Protection System Work Supply, Installiation, testing & commissiong of 8 mm Aluminum Round Conductor OBO Type No. RO B ALUI (14-50086)	250.00	Mtr	INR		0.00		INR Zero Only
165	Supply, installation, testing & commissiong of Roof conductor holder for parapet- Polyamide Conductor holder Will MB female thread or diameter 7mm, MB Screw to connect the conductor holder. Weather and temperature resistant from -35 to +90 degree Celsius tested. Conductor holder @1 meter case CBO Type No. 177 30 MB (5297460)	320.00	Nos	INR		0.00	0.00	INR Zero Only
166	Supply, installation, testing & commissions of 1 Intr vertical air terminal with mounting accessories on the flat surface to meet the requirements of IS/IEC 62305. Tested for Electrical, mechanical and chemical as per IEC 62561. Tested for 100k1 lightning current. 000 type No.F-PK WINOR (5403308)	8.00	Nos	INR		0.00	0.00	INR Zero Only

Sign and stamp of bidder Sign and stamp of EPIL Name of the Firm / Company

195

199

specification, approved TDS as directed by Engineer in-charge.Make:- Honeywell

Supply, instatllation, testing & commissiong of Fire Fighting Telephone Handset.

Resistance as per BS 8434-2:2003, 930°C rating for three hours for fire alarm system. Approved Make :- RR/Polycab Supply, installation, testing & commissiong 8 zone conventional Fire Fighting Telephone panel

Item Wise BoQ

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

possponding program of the program o

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

	PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN	DUDEEC (IND)	ONII VO					
	(DUMESTIC TENDERS - KALES AKE TO GIVEN IN (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the			ected for this te	nder. Bidders are allowed to	enter the Bidder Nam	e and Values only)	
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	7	13	14	15
167	Supply, installation, testing & commissiong of Lightnig counter - To count no of lightning strike & it can record the date and time of the lightning incident also tested as per IEC 62561-6. 000 (Type No. ISC 141 (15091 72 2)	1.00	Nos	INR		0.00		INR Zero Only
168	Supply, instatllation, testing & commissiong of T 160 0E HD TR Junction Box - IP 66, IK10 Transperant Junction Box for Lightning Counter.	1.00	Nos	INR		0.00	0.00	INR Zero Only
169	Down conductor Supply, installiation, testing & commission of Test Joint (Folding Clamp) suitable to connect 8mm round conductor and max by 30x3 mm GI strip as specified in drawing and directed by Engineer. Tested for 100kA lightning current LOBO Type No. 271 8-10 [5317401]	13.00	Nos	INR		0.00	0.00	INR Zero Only
170	Ring & vertical earthing system Supply, instatilation of Cross connector for Flat: Suitable for 30mm Galvanised steel strip. Installed with 4 nos of hexagonal plate. OBO Type No. 255 FL30 FT (5314534)	22.00	Nos	INR		0.00	0.00	INR Zero Only
171	Supply of flat conductor holder- Fit: Ft. 30, With mounting hole 6.2 x 22 mm, With 2 cylinder bolts M6 x 16 and over-piece from hot-dip galvanised steel, Bottom section from polyamide, black OBO Type No. 833 35 (503333)	26.00	Nos	INR		0.00	0.00	INR Zero Only
172	Supply, instatllation of Plastic Corrosion Protection strip: Approx 1.1 mm thick. Width 50mm. Made of petrolatum-coated chemical fibre fabric. OBO Type No.356 50 (2360055)	2.00	Nos	INR		0.00	0.00	INR Zero Only
173	Supply of Galvanised Steel Flat 30X3 mm thickness from earth electrode directly in ground as required. Flat conductor Hot Dipped Galvanized. 1080 Type No. 505 2 DN 30X3 (5 454-945)	295.00	Mtr	INR		0.00	0.00	INR Zero Only
174	UPS Supply, Installation, Testing and Commissioning of 2 X 100% modular redundant 45kVA UPS System with Static By-pass and 2X 100% Lead Acid SMF VRLA Battery Bank, Servo with 30 Mins back up shall be provided for providing power supply to Desktop) Workstations through output UPS Distribution Boards and associated works complete in all respects as per scope of work, Approved TDS as directed by Engineer in-charge. Make-Emerson	1.00	Nos	INR		0.00	0.00	INR Zero Only
175	Supply, Installation, Testing and Commissioning of 100% conventional non redundant 25kVA UPS System with 100% Lead Acid SMF VRLA Battery Bank with 30 Mins back up shall be provided for providing power supply to Desktop/ Workstations through output UPS Distribution Boards and associated works complete in all respects as per scope of work, Approved TDS as directed by Engineer in-charge. Make-Emerson	1.00	Nos	INR		0.00	0.00	INR Zero Only
176	SAFETY AND FIRE PROTECTION EQUIPMENTS Providing and fixing M.V. danger notice plate of 200 mm X 150 mm, made of mild steel, atleast 2mm thick, and vitreous enamelled white on both sides, and with inscription in single red colour on front side as required.	2.00	Nos	INR		0.00	0.00	INR Zero Only
177	Providing and fixing HT danger notice plate of 250 mm X 200 mm, made of mild steel, atleast 2mm thick, and vitreous enamelled white on both sides, and with inscription in single red colour on front side as required.	2.00	Nos	INR		0.00	0.00	INR Zero Only
178	Supply and fixing framed covered with laminated shock treatment chart in English , Hindi & Local language.	1.00	Nos	INR		0.00	0.00	INR Zero Only
179	Supply and fixing framed covered with laminated Main Panel SLD in electrical room as per IE rules fixed to wall as required.	1.00	Nos	INR		0.00		INR Zero Only
180	Supply, installation, testing and commissioning of Standard First aid box (Medic 1500) complete with all accessories as required.	1.00	Nos	INR		0.00		INR Zero Only
181	Supply, installation of Co2 type duly refilled 4.5 Kg & ready to use	27.00	Nos	INR		0.00		INR Zero Only
182	Supply, installation of 4kg ABC type Fire extinguisher	27.00	Nos	INR		0.00		INR Zero Only
183	Providing & fixing 4 nos. fire buckets with stand.	1.00	Nos	INR		0.00		INR Zero Only
184	Providing & fixing of 'No Smoking' and 'No Unauthorized Entry' signboards in English and Hindi, as per IPR- 1970.	1.00	Nos	INR		0.00	0.00	INR Zero Only

Supply and laying of 2 mm thick 1000mm wide chequered rubber mat with ISI mark suitable for 1.1 KV installation.

STIC of Autoglo Photoluminescent Signages & Plan for CCC Building including basement area.

Usakoning, Approval and Obtaining ECI Gerificate from Electrical Inspector, Spicety pet A. 8 Other Opet. If any for all existing along with new Electrical, HVAC, etc installations, preparation of As-built drawings of all installation. 10.00 Sqmtr 0.00 INR Zero Only 185 INR 0.00 1.00 INR 0.00 0.00 INR Zero Only 186 Ls 187 1.00 Ls INR 0.00 0.00 INR Zero Only CCC Building as per the requirement to complete the job Testing & Commissioning of 2 nos CSS, RMU, LT panels, 2 Nos 625 kVA DG set etc with required fuel, servicing, consumable items etc with all respect to complete the job. 1.00 INR 0.00 0.00 INR Zero Only 188 Ls ANALOGUE ADDRESSABLE FIRE DETECTION AND ALARM SYSTEM Supply, instatliation, testing & commissiong (SITC) of Analog Addressable Fire Alarm Control panel with battery back up for 24 hours normal operation and 15 minutesalarm operation. The control panel, battery charger etc, shall be UL listed ditto but 4 loop panel with 99 detectors & 99 modules &upto 200 detectors and modules (per each loop). The Fire Alarm Control Panel shall include a full featured operator interface control and annunciation 1.00 Nos INR 0.00 0.00 INR Zero Only panel that shall include a backlit 840character or Better display, individual, color coded system status LEDs, and keypad for the field programming and control of the fire alarm system. Each Loop shall support a minimum of 125 addressable detectors and 125 devices. The system shall be capable of 3072 annunciation points per system regardless of the number of addressable devices. The panel shall be UL listed and FM approved and comply UL 864, 9th Edition requirement. The enclosure shall also be UL listed. The quoted rate shall include SITC of necessary software and harware for progamming the panel with all necessary licence. As per Technical specification, approve TDS as directed by Engineer in-charge Make:- Honeywell Supply, installiation, testing & commissiong (SITC) of UL listed Intelligent Addressable Multi-Criteria smoke cum Heat detector, optical type with blinking LED and standard base, being capable of being addressed electronically Manual Addressing (Dip/ Rotary Switches) not acceptable. complete with base as required. As per Technical specification, approved TDS as directed by Engineer in-charge Make:- Honeywell 206.00 0.00 0.00 INR Zero Only Supply, instatllation, testing & commissiong (SITC) of UL Listed Addressable control module complete as required for switching ON of smoke extraction fans / Pressurisation Fans etc. and switching off AHU's, capable of being 0.00 INR 0.00 INR Zero Only 191 addressed electronically. Manual Addressing (Dip/ Rotary Switches) not acceptable, complete as required and as per specifications. As per Technical specification, approved TDS as directed by Engineer in-charge. Make: 42.00 Nos Honexwell
STIC of Analogue Addressable Control relay module having Rotary, decimal addressing system for AHU tripping and shall be capable of providing DPDTcontact rated at 24v DC, 2A. As per Technical specification, approved TDS as 192 3.00 INR 0.00 0.00 INR Zero Only Nos directed by Engineer in-charge Make:- Honeywell United by Uniquies in Classification (Control of the Control of th 3.00 Nos INR 0.00 0.00 INR Zero Only 0.00 INR Zero Only 194 the Module to be included), capable of being addressed electronically. Manual Addressing (Dip/ Rotary Switches) not acceptable, with seperate power SITC arrangement complete as required. As per Technical specification, 19.00 Nos INR 0.00 approved TDS as directed by Engineer in-charge. Make:- Honeywell
STIC of Addressable Break Glass Manual Call Point having Rotary, decimal addressing system and having an integrally mounted addressabla module that monitors and reports contact status. UL Listed. As per Technical

Sign and stamp of bidder Sign and stamp of EPIL

17.00

100.00 Nos

1500.00 RM

> 1.00 Nos

14 00 Nos

Nos

INR

INR

INR

INR

INR

0.00

0.00

0.00

0.00

0.00

0.00 INR Zero Only

Item Wise BoQ

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder/ Bidding Firm / Company PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN RUPEES (INR) ONLY)

	(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else th	RUPEES (INR) e bidder is liat	ole to be rej	ected for this te	nder. Bidders are allowed to e	enter the Bidder Name	and Values only)	
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	4	5	12	7	13	14	15
200	Supply, instatliation, testing & commissiong of Fire Fighting Telephone Jacks.	14.00		INR		0.00		INR Zero Only
201	Supply, instatllation, testing & commissiong of GSM Dialer for 5 numbers	1.00	Nos	INR		0.00	0.00	INR Zero Only
202	Supply, instatllation, testing & commissiong of Repeater Panel with 168 Character LCD Display, repeater Panel CPU should have the same intelligence and capability of panel CPU. UL Listed & FM approved	1.00	Nos	INR		0.00	0.00	INR Zero Only
203	PUBLIC ADDRESS SYSTEMS SIT Cot 8 zone IP based, digital Voice Alarm controller expandable upto 128 zones each controller shell be capable of including 4 channel and minimum 500 Watts. The voice alarm controller should be able to connect directly owner thement. It should have functions like the audio playing, zone control, fault monitoring, log recording, volume control and amplifier switchover. The Voice alarm controller should also have the following functions: 255 Proorlies and 256 Zone. Time schedule broadcasts. Capable of amplifier redundancy. 4 trigger inputs/outputs. As per Technical specification, approved TDS as directed by Engineer in-charge Make:- Honeywell	1.00	Nos	INR		0.00	0.00	INR Zero Only
204	SITC of 1X500 W Class-D Amplifier with 1 independent channel and can provide automatic resettable overcurrent, overload, overheating, overvoltage, under-voltage and DC protection. As per Technical specification, approved TDG as a directed by Engineer inc-hange, Make: Honorewell	2.00	Nos	INR		0.00	0.00	INR Zero Only
205	SITC of IP based Networkable touch screen paging station for selection of zones, supervision of system status, setting of scheduled broadcasts with the following functions: Built-in monitoring loudspeaker. Detachable goose-neck microphone. LCI touchscreen display. Audio injunk. A sper Technical specification, approved TDS as directed by Engineer in Engage Make: -Honeyening Make: Thorogram (Supervision State Sta	1.00	Nos	INR		0.00	0.00	INR Zero Only
206	SITC of UL Listed 6 W False Celling/Surface Mounted speaker with capacity to have 1/4,1/2,1 and 2 watt tapping, working at 83dB compatible with amplifier complete as required. As per Technical specification, approved TDS as directed by Engineer in-charge. Make: Honoeywell	130.00	Nos	INR		0.00	0.00	INR Zero Only
207	SITC of UL Listed 2way 6 W Surface/wall Mounted speaker with capacity to have 1/4,1/2,1 and 2 watt tapping, working at 83dB compatible with amplifier complete as required. As per Technical specification, approved TDS as	23.00	Nos	INR		0.00	0.00	INR Zero Only
	directed by Engineer in-charge Make: Honeywell SITT 2 core twin twisted 48/02 2 ATC, Multi strand, over all armoured speaker cable as specified in the Tender Specifications.	1000.00		INR		0.00		INR Zero Only
209	CCTV SYSTEMS SIT Cd Workstation PC: Intel(R) Core[TM) (7-3770 Processor (8M Cache, up to 3.90 GHz); Memory: 4GB, NON-ECC, 1600MHz; RAM: 4GB (1x4GB) Non-ECC DDR3 1600MHz SDRAM Memory; Keyboard: 12 function keys; Chassis: Tower/Workstation; DVD: 8X Slimline DVD-FRW, Data Only; 20° TFT Monitor; Dual Graphics Card; Network interface card: Integrated intel(R), 82579LM Gigabital Ethernet LAN 10/100/1000; Hard disk: 250GB, 7200 RPM 3.5° SATA 6GB/s Hard Drive; Operating system: Windows 7 Professional 64 Bit As per Technical specification, approved/complying commented TDS as directed by Engineer in-charge.	1.00	Nos	INR		0.00	0.00	INR Zero Only
	SITC of Full HD 65" LED Professional Display Panel.	1.00		INR		0.00		INR Zero Only
211	SITC of 24 Port PDE Layer 2 Switch with 2 SFP Port Addressing (Dipl/ Rotary Switches) not acceptable. complete with base as required. Approved Make :-Digisol STR of 24 port Cart 6 patch panels equipped with tool pois 10, Rack Mountable. 197 Modular Patch Panel, loaded CAT6 (U/LTP 24 port LApproved Make is its: Legrand	4.00 4.00		INR INR		0.00		INR Zero Only INR Zero Only
213	SITC of 2 Point: An opening passers passes suppress with the top state of the state	42.00		INR		0.00		INR Zero Only
214	SITC of 6TB HDD	4.00		INR		0.00		INR Zero Only
215	SITC, installation, testing and commissioning of UL Listed 2 MP bullet camera, as per Technical specification, approved TDS as directed by Engineer in-charge.	7.00	Nos	INR		0.00		INR Zero Only
216	SITC UL Isted 3 MP Dome Camera, as per Technical specification, approved TDS as directed by Engineer in-charge. SITC of AUD Network Rack with 1979/DU 6 points 5 amp, stationary sheef, Mounting Hardware pac Of 101, Cable manager Horizontal 1U, Fan 230 vac 90 cfm top mounted As per Technical specification, approved TDS as	33.00	Nos	INR		0.00		INR Zero Only
217	directed by Engineer in-charge. Approved Make :- LEGRAND	1.00	Nos	INR		0.00	0.00	INR Zero Only
218	SITC of UTP 4 pair CAT 6 LAN Cable in the surface/ recessed including HMS FRIS PVC conduit as required. 4 Pair CAT 6 Universided, Twisted Pair (U/UTP) conforming to the following standards like ANSI/TIA 568 C.2, ENSD173, IEC 11801 2nd ED, DOMONIte etc. In Cat 6 U/UTP LCS2 cable with 23AWG. Approved Make list; 1-ca61-Legrand, Conduit-AKG/PercLision	1250.00	RM	INR		0.00	0.00	INR Zero Only
219	SITC of 4 STB (8x 6 TB 7.2k RPM SATA Enterprise Graqde 6 Gbon 3.5 in Hot- plug Hard Drive), Embedded Linux / windows 2012 R2 Server, Quad Gigabit Ethernet interfaces, Hardware Raid controller to support Raid 0.1.5 6 or more, preinstalled VMS. Licenses required to activate camera Channels, Dual Redundant PSU,DVD+/-RW Drive, Rack. As per Technical specification, approved TDS as directed by Engineer in-charge.	1.00	Nos	INR		0.00	0.00	INR Zero Only
220	DATA & VOICE NETWORKING SYSTEM SITC of 24 Port Layer 2 Switch with 2 SPP Port Addressing (Dip/ Rotary Switches) not acceptable. complete with base as required. As per Technical specification, approved TDS as directed by Engineer in-charge.	8.00	Nos	INR		0.00	0.00	INR Zero Only
221	STIC of Cat 6, Tool less Information outlet for Data Cat6 U/JUTP built in crimping handsfree, minimum 5 times reconnection possibilities. LCS2 Toolless RMS information outlet where insertion test (in & out) must be 2500 times (I/O) along with front side Label holded and transparent shutter for projection in exhisting front plate and back box in concealed/surface manner of adequate sizes, including all fixing accessories. Approved Make: Legrand (ILuncus, White)	190.00	Nos	INR		0.00	0.00	INR Zero Only
222	SITC of R.11 Telephone socket for Voice. R.1 Invoice outlet along with front side Label holded projection in exhisting front plate and back box in concealed/surface manner of adequate sizes, including all fixing accessories. Approved Make: tegrand (Lyncus, White)	95.00	Nos	INR		0.00	0.00	INR Zero Only
	Supply, Installation, Testing & commissioning of 100 Pair DP Box with Krone Module and all other materials as required. Make - Krone/Similar.	5.00		INR		0.00		INR Zero Only
224 225	Supply, Installation, Testing & commissioning, of 2 pair Telephone cable as per approved TDS as directed by Engineerie in-charge, Make-Polycab ETP of 6.5 Early, 2.75 ETF (17.3 24 MD Dath Cod.). The Pack End. Extraceris	1000.00 104.00		INR INR		0.00		INR Zero Only INR Zero Only
226	SITC of A feet: CATE UTP 23 AMG Patch Cord - 1 mtr- Rack End. Factory crimped LCS2 Patch cord in Blue colour. Approved Make: Lenslands, STIC and feaving of UTP 4 pair CAT 6 LAN Cable in the surface, recessed including HMS FRLS PVC conduit as required. 4 Pair Cate, United A visited Pair (U/UTP) conforming to the following standards like ANS/TIA 568 C.2, EM50173, IEC 11001 2 nd 610, 7000Hin et c. in Cat 61 U/UTP LCS2 cable with 23AMG Approved Make List: - Cat6-Legrand, Conduit-AKG/Perckion	500.00	Mtr	INR		0.00		INR Zero Only
227	Supply, instatllation, testing & commissiong (SITC) of Wifi ACESS POINT along with all accessories as per Technical specification, approved TDS as directed by Engineer in-charge	13.00		INR		0.00		INR Zero Only
228	Supply, installation, testing & commissiong (SITC) of 12 POT OFC UIU 80X along with all accessories as per Technical specifications, approved TDS as directed by Engineer in-charge	4.00		INR		0.00		INR Zero Only
229	Supply, installation, testing & commissiong (STC) of 6 POT OFC LU BOX along with all accessories as per Technical specification, approved TDS as directed by Engineer in-charge Supply, installation, testing & commissiong (STC) of 5 POTFEL along with all accessories as per Technical specification, approved TDS as directed by Engineer in-charge	2.00 60.00		INR INR		0.00		INR Zero Only INR Zero Only
231	Supply, installation, testing & commissioning faircy or 3c Profits along with an accessories as per recurricus specification, approved 1033 and unetween by cingineer in-change (Supply, installation, testing & commissioning (STC) of DUE MODUL TRANSFECIVER along with all accessories as per Technical specification, approved 105 as directed by Engineer in-change	10.00		INR		0.00		INR Zero Only
232	Supply, instatllation, testing & commissiong (SITC) of SCTO LC PATCH CORD along with all accessories as per Technical specification, approved TDS as directed by Engineer in-charge	10.00	Nos	INR		0.00		INR Zero Only
233	Supply, instatllation, testing & commissiong (SITC) of 15 U WALL MOUNTED RACK WITH ALL ACCORIES along with all accessories as per Technical specification, approved TDS as directed by Engineer in-charge	3.00	Nos	INR		0.00		INR Zero Only
234	Supply, installiation, testing & commissiong (SITC) of OFC & CORE FIBER along with all accessories as per Technical specification, approved TDS as directed by Engineer in-charge HVAC WORKS	500.00	RM	INR		0.00	0.00	INR Zero Only
235	E) HVAC. WUCKS. Supply, Installation, Testing & Commissioning of Floor mounted DX Type double skin air handling units, including refrigerant topup, civil foundation etc. as required to complete the job as per approved technical data sheet complying all the comments/specification. Make-Zeco 11400 CFM, 285 TR	1.00	Nos	INR		0.00	0.00	INR Zero Only

Sign and stamp of bidder 9 Sign and stamp of EPIL

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the

Content Traces and Content and	ne of the der/ Bidding n / Company								
Part		DRIAG ANTENNA							
No.		(DOMESTIC TENDERS - RATES ARE TO GIVEN IN F				adas Biddass ass allawad to a	onto the Didder New		
No.		(I his BOQ tempiate must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the	bidder is ilab	le to be rej	ected for this te	nder. Bidders are allowed to e		• •	
Buyer, installation, button good commissioning of East Author The Author Companies of the Open Special Conference and Conferen		Item Description	Quantity	Units	Currency in INR / Other	Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in	Without Taxes in	With Taxes in	TOTAL AMOUNT In Words
Section in single for maximum influstry the case of substants to an activation to an activation of the process of the maximum influstry the case of substants to an activate of substant in the process of the process	1	2	4	5	12	7	13	14	15
100 CPU 100	237	pitch angle for maximum efficiency Die cast aluminium hub and blades - Long casing, hot dip galvanized steel, to DIN EN ISO 1461- Three-phase IEC motors, IPSS, Suitable for operating temperatures of up to 55°C-For fire application finas should be Suitable for operating temperatures of up to 55°C-For limit (Fasted in accordance to EN 12101-32002) The motor should have speed controllable by frequency converter.including Spring isolator, necessary supports etc.Static Pressure and other specifications as per the approved technical specification complying all the comments, as per direction of Engineer-in-charge. Make-Yurge. Make-Yurge.	2.00	Nos	INR		0.00	0.00	INR Zero Only
100 1000 CPM									
100 200 CFM									
2000 CFM									
Sport Spor									
Bugsyl, institution, stating & commissioning of California from Fam with Double Nett Double With Drived Driver Fam with single skin regign or connected on the quantitation relater from Annual Properties of the position of the global seas. Bugsyl properties of the position of the global seas. Bugsyl properties of the position of the global seas. Bugsyl properties of the position o									
160 CPM 200 PM 2	244	Supply, installation, testing & commissioning of Cabinet Inline Fans with Double Inlet Double Width Direct Driven Fan with single skin supply or extract box fans for inline applications. Robust and quiet operation to the galvanized steel fan and motor support mounted on antivibration rubber plots. Outlet connected to the casing through a canves joint acting as a flexible seal. Square air inlet and rectangular air outlet. Efficient double inlet galvanized steel forward curved impeller balanced statical ady anyamically, Operates with air up to 50°C. Static Pressure and other specifications as per the approved technical specification complying all the comments as per direction of Engineer-in-charge. Make-Kurger 1000 CFM.	16.00	Nos	INR		0.00	0.00	INR Zero Only
200 CPM Supply, installation, testing & commissioning of Circular terms Fam. with Fam. Speek-controllate with theight thermal contexts The Fam about to designed for mutalisation in ducts with carbon be speed controlled via a staphesistyristor or a Supply installation, testing & commissioning of Propeller Fam (page and selected for motion) with the present of the Earth Fam. Supply, installation, testing & commissioning of Propeller Fam (page and selected for Management of Propeller Fam (page and selected for									
Supply, installation, selling & commissioning of tricular finiter has with Fair Speed-controllate with bidgery thermal contents. The fair with the fair subscribed of the state of the state of the state of the cut. The fair subscribed of the state of the state of the duct. The fair subscribed of the state of the stat								0.00	INR Zero Only
Supply, Installation, testing & commissioning of Propeller Fans (puto 200 CFM) The fan is suitable for wall mounting. Condenser motor with thermo cut-off. Well lubiricated bearing for long life operation. Propeller fan incorporated with advance blade design enables powerful airflow at low noise. Automatic shutter. Office equipped with oil cup collects oil drops effectively. Front louver with bind shutter enhances privacy and safety protection. Frame in smartifactured from ABS Plasts materials aper approved technical specification. Make-Kurger		Supply, installation, testing & commissioning of Circular Inline Fans with Fan Speed-controllable with integral thermal contacts The Fan should be designed for installation in ducts with minimum 25 mm long spiped connections. The fans will have backward-curved blades and external rotor motors with mounting clamp to prevent the transfer of vibration to the duct. The fans can be speed-controlled via a steplessthyristor or a 5-step transformer. The casing is manufactured from galvanised sheet steel and folded which gives the fan a close to air tight casing. Static Pressure and other specifications as per the approved technical specification comments.as per direction of Engineer-in-charge. Make-Kurger							,
supply, installation, testing & commissioning of Propeller Fans (pape 200 CFM). The fan is suitable for wall mounting, Condenser motor with thermose cut-off. Wall lubricated bearing for long life operations. Propeller fan is commissioning of propeller fans (pape 200 CFM). 25.1 DO CFM 25.2 DO CFM 25.3 DO CFM 25.3 DO CFM 25.4 Supply, installation, testing & commissioning of Propeller Fans (above 200 CFM) with square plate for wall mounting. Protection guard on the inlet External rotor motor The fan casing, protection guard and propeller are manufactured from palvanized setel, parined in standard black. The fans have sickle bladed imposlingers are paragroved technical specification, white-Runger 25.3 Design, Supply, installation, testing & commissioning of Propeller Fans (above 200 CFM) with square plate for wall mounting. Protection guard on the inlet External rotor motor The fan casing, protection guard and propeller are manufactured from palvanized setel, parined in standard black. The fans have sickle bladed imposlingers are approved technical specification, white-Runger 25.0 Design, Supply, installation, testing & commissioning of APU & Vertilation Fan Starter Panel as per approved technical specification, as per direction of Engineer-in-charge, as per approved make. 25.1 EVM, 3-phase, Star Delta Starter 25.2 EVM, 3-phase, Star Delta Starter 25.3 FOW, 3-phase, Star Delta Starter 25.4 To FOW, 3-phase, Star Delta Starter 25.5 EVM, 3-phase, Star Delta Starter 25.6 STAW, 3-phase, Star Delta Starter 25.6 STAW, 3-phase, Star Delta Starter 25.7 EVM, 3-phase, Star Delta Starter 25.8 To FOW, 3-phase, Star Delta Starter 25.9 Nos. 25.9 Nos. 25.9 Nos. 25.9 Nos. 25.9 Nos. 25.0	249		1.00	Nos	INR		0.00	0.00	INR Zero Only
Supply, installation, testing & commissioning of Propeller Fans (above 200 CFM) with square plate for wall mounting. Protection guard on the inlet External rotor motor The fan casing, protection guard and impeller are manufactured from galvanized steel, painted in standard black. The fans have sickle bladed impellers, as per approved technical specification, Make-Kurger 20 Nos INR 23 Design, Supply, installation, testing & commissioning of AHU & Ventilation Fan Starter Panel as per approved technical specification, as per direction of Engineer-in-charge, as per approved make. 20 Nos. INR 24 7, 5KW, 3-phase, Star Delta Starter 25 5, 5KW, 3-phase, Star Delta Starter 26 7, 3KW, 3-phase, Direct On Line (DOL) Starter 27 20 Nos. INR 28 1, 5KW, 3-phase, Direct On Line (DOL) Starter 28 1, 5KW, 3-phase, Direct On Line (DOL) Starter 29 2, 2KW, 3-phase, Direct On Line (DOL) Starter 20 Nos. INR 20 Nos.	250	operation. Propeller fan incorporated with advance blade design enables powerful airflow at low noise. Automatic shutter. Orifice equipped with oil cup collects oil drops effectively. Front louver with blind shutter enhances privacy and safety protection. Fan is manufactured from ABS Plastic material. as per approved technical specification. Make-Kurger	3.00	Nos	INR		0.00	0.00	INR Zero Only
200 Nos NR 0.00 0.00 NR Zero Only	251	200 CFM	5.00	Nos	INR		0.00	0.00	INR Zero Only
11 KW, 3-phase, Star Delta Starter	252	and impeller are manufactured from galvanized steel, painted in standard black. The fans have sickle bladed impellers as per approved technical specification. Make-Kurger	2.00	Nos	INR		0.00	0.00	INR Zero Only
25 S. S. RW, 3 phase, Direct On Line (DOL) Starter 1.00 Nos. NR 0.00 0.00 NR Zero Only 25 2.2 RW, 3 phase, Direct On Line (DOL) Starter 2.00 Nos. NR 0.00 0.00 NR Zero Only 25 2.2 RW, 3 phase, Direct On Line (DOL) Starter 2.00 Nos. NR 0.00 0.00 NR Zero Only 25 2.2 RW, 3 phase, Direct On Line (DOL) Starter 3.00 Nos. NR 0.00 0.00 NR Zero Only 25 3.5 RW, 3 phase, Direct On Line (DOL) Starter 3.00 Nos. NR 0.00 0.00 NR Zero Only 25 3.5 RW, 3 phase, Direct On Line (DOL) Starter 3.00 Nos. NR 0.00 0.00 NR Zero Only 26 3.5 RW, 3 phase, Direct On Line (DOL) Starter 3.00 Nos. NR 0.00 0.00 NR Zero Only 27 4.0 Core 18 ogmm copper amoured cable 200.00 Mtr NR 0.00 0.00 NR Zero Only 28 4.0 Core 18 ogmm copper amoured cable 450.00 Mtr NR 0.00 0.00 NR Zero Only 26 4.0 Core 19 ogmm copper amoured cable 230.00 Mtr NR 0.00 0.00 NR Zero Only 26 5.0 Spyl, & faing of Individual rain protected isolator (IP 65) 63 amps incluiding DB box complete with connections, testing and commissioning etc. as required. as per approved make. 5.00 Nos NR 0.00 0.00 NR Zero Only 26 5.0 Spyl, Installation, Testing & Commissioning of Acrotic expansion valve et as required. Assert 6 5.00 Nos NR 0.00 0.00 NR Zero Only 26 5.0 Spyl, Installation, Testing & Commissioning of Cordel Remote Controller. Make-LG 5.00 Nos NR 0.00 0.00 NR Zero Only 27 5.0 Spyl, Installation, Testing & Commissioning of Cordel Remote Controller. Make-LG 5.00 Nos NR 0.00 0.00 NR Zero Only 28 5.0 Spyl, Installation, Testing & Commissioning of Cordel Remote Controller. Make-LG 5.00 NR Zero Only	253		3.00	Nos.					,
2.5 3.7 kW, 3-phase, Direct On Line (DOL) Starter									
22 KW, 3-phase, Direct On Line (DOL) Starter									
Supply & S									
Supplying_Jaying and making end termination of one number PVC insulated armoured and PVC sheathed Cu conductor power cable of 1.1 KV grade of following size cables as required to complete the job. [MAKF-Polyxab]									
4 Core 10 symm copper armoured cable		Supplying, laying and making end termination of one number PVC insulated armoured and PVC sheathed Cu conductor power cable of 1.1 KV grade of following size cables as required to complete the job.[MAKE-Polycab]							
Supply & fixing of Individual rain protected isolator (IP 65) 63 amps incluiding DB box complete with connections, testing and commissioning etc. as required. as per approved make. 5.00 Nos INR 0.00 0.00 INR Zero Only Supply, Installation, Testing & Commissioning of Arabity installation, Testing & Commissioning of Cordels Remote Controller. Make-LG 5.000 Nos INR 0.00 0.00 INR Zero Only Nos INR 0.00 0.00 INR Zero Only Nos INR 0.00 0.00 INR Zero Only Supply, Installation, Testing & Commissioning of Cordels Remote Controller. Make-LG 5.000 Nos INR 0.00 0.00 INR Zero Only Supply, Installation, Testing & Commissioning of Cordels Remote Controller. Make-LG 5.000 Nos INR 0.00 0.00 INR Zero Only Supply, Installation, Testing & Commissioning of Cordel Remote Controller. Make-LG 5.000 Nos INR 0.00 0.00 INR Zero Only Supply, Installation, Testing & Commissioning of Sichibation Injoint (Indoor Unit), Make-LG 5.000 Nos INR 0.00 0.00 INR Zero Only Supply, Installation, Testing & Commissioning of Sichibation Injoint (Indoor Unit), Make-LG 5.000 Nos INR 0.00 0.00 INR Zero Only Supply, Installation, Testing & Commissioning of Sichibation Injoint (Indoor Unit), Make-LG 5.000 Nos INR 0.00 0.00 INR Zero Only									
263 Supply & fixing of rain protected isolator (IP 65) 32 amps including DB box complete with connections, testing and commissioning et. as required. as per approved make. 264 Supply, Installation, Testing & Commissioning of Artl kit comprising, sensors and electronic expansion valve et as required. Make-LG 265 Supply, Installation, Testing & Commissioning of Cordless Remote Controller. Make-LG 260 Supply, Installation, Testing & Commissioning of Cordless Remote Controller. Make-LG 261 Supply, Installation, Testing & Commissioning of Cordles Remote Controller. Make-LG 262 Supply, Installation, Testing & Commissioning of Cordles Remote Controller. Make-LG 263 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 264 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 265 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 266 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 267 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 268 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 269 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 260 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 260 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 261 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 262 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 263 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 264 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 265 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 266 Supply, Installation, Testing									
264 Supply, Installation, Testing & Commissioning of AHU Kit comprising sensors and electronic expansion valve etc as required.Make-LG 1.00 Nos NR 0.00 0.00 NR Zero Only									,
265 Supply, Installation, Testing & Commissioning of Cordes Remote Controller. Make-LG 50.00 Nos INR 0.00 0.00 INR Zero Only 266 Supply, Installation, Testing & Commissioning of Corded Remote Controller. Make-LG 3.00 Nos INR 0.00 0.00 INR Zero Only 267 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit), Make-LG 18.00 Nos INR 0.00 0.00 INR Zero Only	264	Supply, Installation, Testing & Commissioning of AHU Kit comprising sensors and electronic expansion valve etc as required. Make-LG			INR			0.00	INR Zero Only
266 Supply, Installation, Testing & Commissioning of Corded Remote Controller. Make-LG 3.00 Nos INR 0.00 0.00 INR Zero Only 267 Supply, Installation, Testing & Commissioning of distribution joint (Indoor Unit). Make-LG 18.00 Nos INR 0.00 0.00 INR Zero Only		Supply, Installation, Testing & Commissioning of Cordless Remote Controller. Make-LG	50.00	Nos	INR		0.00	0.00	INR Zero Only
		Supply, Installation, Testing & Commissioning of Corded Remote Controller. Make-LG							
268 Supply, Installation, Testing & Commissioning of distribution joint (Outdoor Unit). Make-LG 6.00 Nos INR 0.00 0.00 INR Zero Only	267 268		18.00 6.00	Nos Nos	INR INR		0.00		

Item Wise BoQ

Tender Inviting Authority: ENGINEERING PROJECTS (INDIA) LTD., PCO Bhubaneswar

Name of Work: Tender for Execution of balance works in CCC building such as civil, sanitary & plumbing works, internal electrical works, ICT works & HVAC works at RourkelaONE project, Rourkela, Sundergarh Dist., Odisha

Contract No: PCO/BBSR/806/159 Dt.29.02.2024

Name of the Bidder/ Bidding Firm / Company :								
	PRICE SCHEDULE (DOMESTIC TENDERS - RATES ARE TO GIVEN IN (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else th			ected for this te	nder. Bidders are allowed to e	nter the Bidder Name	e and Values only)	
SI. No.	Item Description	Quantity	Units	Quoted Currency in INR / Other Currency	BASIC RATE (including Transportation Insurance, F.O.R.) In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT With Taxes in Rs. P	TOTAL AMOUNT in Words
1	2	4	5	12	7	13	14	15
269	BMS Controller	1.00	Nos	INR		0.00	0.00	INR Zero Only
270	Supply, installation, testing and commissioning of the following sizes Cu. refrigerant pipes duly insulated with 19mm/13mm close cell elastometric nitrite rubber insulation between each set of outdoor and indoor units (VRF) including cable tray, cover plate for outdoor area angle, supports etc as required a directed by engineer-in-charge, as per approved technical specification. Class O. Make-Rajco 41.3 mm outer dia with 19 mm thick insulation.	27.00		INR		0.00		INR Zero Only
	38.1 mm outer dia with 19 mm thick insulation.	10.00		INR		0.00		INR Zero Only
	34.9 mm outer dia with 19 mm thick insulation.	70.00		INR		0.00		INR Zero Only
	28.6 mm outer dia with 19 mm thick insulation.	71.00 15.00		INR INR		0.00 0.00		INR Zero Only
275	15.9 mm outer dia with 9 mm thick insulation. Supply, installation, testing and commissioning of PVC pipe (For drainage of water from IDU, AHU) with 12 mm thick Nitrile Rubber insulation, clamp, supports etc as required as per approved technical specification. 40 mm NB	15.00	mtr	INR		0.00		INR Zero Only INR Zero Only
	32 mm NB	40.00	mtr	INR		0.00	0.00	INR Zero Only
	25 mm NB	40.00	mtr	INR		0.00	0.00	INR Zero Only
	Supply, installation, testing & commissioning of Communication cabling between ODU and IDU including PVC HMS FRLS conduits etc as per OEM Specification. 2 core x 1 Sqmm FRLS	100.00	mtr	INR		0.00		INR Zero Only
279	Supply, installation, testing & commissioning of GSS ducting of following thickness including necessary supports, adjustable dampers, vanes etc complete as per 15 655/ as per approved technical specification.Make-Sail 18 Gauge GSS Ducting Site - fabricated	50.00	Sqmtr	INR		0.00	0.00	INR Zero Only
	20 Gauge GSS Ducting Site - fabricated	60.00	Sqmtr	INR		0.00	0.00	INR Zero Only
	22 Gauge GSS Ducting Site - fabricated	60.00	Sqmtr	INR		0.00	0.00	INR Zero Only
282	24 Gauge GSS Ducting Site - fabricated	80.00	Sqmtr	INR		0.00	0.00	INR Zero Only
	Supplying and fixing of acoustic lining of duct with Open Cell Nitrile Rubber density 140-180 Kg/m3. Applied by Adhesive, conforming to standard specification/as per approved technical specification. 10 mm thick open cell nitrile rubber.	25.00	Sqmtr	INR		0.00	0.00	INR Zero Only
284	Supply, installation, testing and commissioning of Thermal Insulation of Ducts with Closed cell elastomeric nitrile rubber insulation on duct surface area. The density of material shall be 40 to 60 kg/m3 fire rated for Class 0. Ecomplete as per specifications and drawings etc, as per approved technical specification. 19 mm Thick 14 faced	45.00	Sqmtr	INR		0.00	0.00	INR Zero Only
	Under Deck Insulation with 50 mm thk Themocole of density of the material shall be 20 kg/m3 as per approved technical specification.	700.00		INR		0.00		INR Zero Only
	Supplying, fixing, testing & commissioning of power coated extruded aluminium section supply air grills with volume control dampers complete as required. Make-System Air	20.00		INR		0.00		INR Zero Only
	Supplying, fixing, testing & commissioning of power coated extruded aluminium section return air grills with louvers without volume control dampers complete as required.	25.00		INR		0.00		INR Zero Only
	Supplying, fixing, testing & commissioning of power coated extruded aluminium section supply air diffusers with volume control dampers complete as required. Supplying, fixing, testing & commissioning of power coated extruded aluminium section return air diffusers with louvers without volume control dampers complete as required. Make-System Air	10.00		INR		0.00		INR Zero Only INR Zero Only
	Supplying, fixing, testing & commissioning of Firerated Canvass Connection	40.00 9.00		INR INR		0.00 0.00		INR Zero Only INR Zero Only
	Supplying, fixing, testing & commissioning of VCD for Duct	4.00		INR		0.00		INR Zero Only
	Supplying, fixing, testing & commissioning of Coller damper Supplying, fixing, testing & commissioning of Louvers for Fresh Air arrangement	2.00		INR		0.00		INR Zero Only
	Supply, installation & testing of Duct mounted GI Fire Dampers with Actuators as per approved technical specification. as per direction of Engineer-in-charge.	4.00		INR		0.00		INR Zero Only
	Design, Supply, installation, testing & Commissioning of CO sensor including cabling at besement area for ventilation system integrating with ventilation fans, fire system etc as requited to complete the job. as	5.00		INR		0.00		
Total in Figures	per approved technical specification, as per direction of Engineer-in-charge.	5.00	NO	IIVIX		0.00		INR Zero Only INR Zero Only
Quoted Rate in F	iourne				Г			•
QUOTED NATE III F	ngur co					0.00	0.00	Zero Only
Quoted Rate in V	Vords	INR Zero Only						